APPENDIX E
TRIP GENERATION, FREIGHT LOADING, AND PASSENGER LOADING MEMO

This page intentionally left blank

San Francisco Planning

49 South Van Ness Avenue, Suite 1400
San Francisco, CA 94103
628.652.7600
www.sfplanning.org

June 7, 2024

Sherie George, Acting Transportation Team Lead
Environmental Division, San Francisco Planning
49 South Van Ness Ave, Suite 1400
San Francisco, CA 94103

Re: 3400 Laguna Street, Proposed Project Trip Generation
Planning Department File No. 2022-009819ENV

To Whom It May Concern:

Pursuant to the *San Francisco Transportation Impact Analysis Guidelines for Environmental Review*[1], the San Francisco Planning Department prepared the following memo to analyze the potential trips generated from the proposed project at 3400 Laguna Street and whether implementation of the project would result in a passenger or freight loading deficit.

Project Description

The approximately 68,090-square-foot (approximately 1.6-acre) project site at 3400 Laguna Street is located on a corner lot southeast of the Laguna Street and Bay Street intersection in the Marina neighborhood. The site is bounded by Bay Street to the north, single- and multi-family residences near to and along Octavia Street to the east, Francisco Street to the south, and Laguna Street to the west. The project site has been occupied by the Heritage on the Marina residential care retirement community since 1925. Heritage on the Marina consists of five existing structures of approximately 83,200 gross square feet: the Julia Morgan Building, the Perry Building, the Perry Building Connector, the Health Center, and the Caretaker's Cottage. The current number of residential care suites is 86.

The proposed project would continue to operate as a residential care facility. The proposed project would demolish two of the five existing buildings (the Perry Connector and the Health Care Center) and construct two new buildings (the Bay Building and the Francisco Building) of heights not to exceed 40 feet and in the same locations as the demolished structures. The proposed project would renovate two of the other three existing buildings on the site. In total, the proposed project would add approximately 58,380 square feet of institutional use and increase the number of residential care suites by 23, from 86 to 109. Of the total 109 units, approximately 10 may have double occupancy; therefore, a total residential population of 119 is anticipated, or an increase of up to 33 residents compared to 86 residents under existing conditions. At project completion, a total of 75 staff members are expected to be employed at the site, which would be an increase of 22 staff members as compared

[1] San Francisco Planning Department, Transportation Impact Analysis Guidelines for Environmental Review (February 2019, updated October 2019), https://sfplanning.org/project/transportation-impact-analysis-guidelines-environmental-review-update#impact-analysis-guidelines, accessed on May 7, 2024.

to existing conditions. In total, the proposed project would consist of 141,580 gross square feet of institutional use, including 109 residential care units. Further detail is provided in Table 1.

Table 1 Proposed Project Details

Project Component	Existing	Proposed	Net Change
Number of Building(s)	5	5	0
Maximum Building Stories[1]	4	4	0
Maximum Building Height (feet)[1]	41	41	0
Building Gross Square Feet	83,200	141,580	+58,380
Residential Care Units	86	109	+23
Useable Open Space (gross square feet)	26,410	30,280	+3,870
Off-Street Parking Spaces	17	36	+19
Off-Street Loading Spaces	2	1	-1
On-Street Parking Spaces[2]	28	20	-8
On-Street Ride Share Spaces	0	1	+1
On-Street Commercial Loading Spaces	0	0	0
On-Street Passenger Loading Spaces	3	2	-1

Source: HKS Inc. and Kimley-Horn, 2023.
Notes: All gross square feet numbers are rounded to the nearest multiple of 10.
[1] Reflects the maximum building height and number of stories; existing buildings vary across the site. The existing Perry Building is 40.5 feet tall (rounded to 41 feet tall) and no changes to this building's height are proposed. The new Bay and Francisco building heights would not exceed 40 feet.
[2] Reduction in parking due to bulb-outs required by planning code section 138.1. In addition, one on-street parking space on Bay Street would be removed for the project's new driveway; however, one on-street parking space would be added on Francisco Street because the proposed project would eliminate the existing 22-foot passenger loading space on Francisco Street.

The project site currently includes 17 off-street vehicle parking spaces and two off-street loading spaces, which are accessible via the existing 18-foot-wide driveway along Bay Street. The project site has approximately 45 feet of passenger loading (white curb) and 20 feet of accessible parking (blue curb) on the Laguna Street frontage and 22 feet of passenger loading (white curb) on the Francisco Street frontage. Pedestrian access to the site is provided via gates along Laguna Street that access internal sidewalks connecting to the Julia Morgan Building entrances and additional accessible entrances from Bay Street.

The proposed project would construct a new basement level garage beneath the proposed Bay and Francisco buildings and the existing interior courtyard. The basement level would include 31 vehicular parking spaces for use by staff and residents, including one car-share space, and 18 bicycle parking spaces. A new two-directional, 20-foot-wide driveway on Bay Street would provide access to the new basement level garage, east of the existing entrance. Vehicles would be restricted to right-only turns into and out of the driveway. At this location, an approximately 20-foot-long, two-lane off-street covered porte cochère would provide universal access required by the residential care facility. The existing driveway on Bay Street, west of the new driveway, would provide access to five off-street surface parking spaces. (See Appendix A – Proposed Site Plan.)

The new driveway would necessitate the removal of the 17 existing off-street surface parking spaces and approximately 15 feet off-street parking spaces along Bay Street, resulting in the loss of one on-street parking space. However, one on-street parking space would be added on Francisco Street, thus eliminating the existing 22-foot passenger loading space and associated curb cut. Additionally, the project would remove an additional

eight on-street parking spaces for required bulb-outs on the corners of Laguna Street and Fransisco Street and Laguna Street and Bay Street as required by planning code section 138.1. The proposed project would also add 12 bicycle parking spaces in the public right of way (three located on Bay Street and nine located on Francisco Street).

In total the project would remove 8 on-street parking spaces and would add 19 off-street parking spaces. The proposed project would also remove one off-street loading space by reconfiguring the off-street parking to accommodate the new driveway, porte cochère and below-grade garage entrance. Additionally, one on-street passenger loading space would be removed on Francisco Street to add one on-street parking space.

Street Design Advisory Team (SDAT) Review

The project was reviewed in November 2022 by San Francisco Planning's Street Design Advisory Team (SDAT), and a final letter with SDAT feedback was issued to the sponsor on December 12, 2022, as part of the Preliminary Project Assessment Letter (See Appendix B - SDAT Letter, December 2022 and SDAT follow up email, June 2023). The project sponsor complied with SDAT requests regarding bulb out design and proposed driveway changes. On June 7, 2023, SDAT responded to the resubmittal, affirming the sponsor had adequately satisfied previous SDAT comments for Planning's purposes and did not need to return for a full SDAT second meeting (Appendix C).

Trip Generation Analysis

The trip generation analysis typically calls for calculating the total person and vehicle trips estimated from residential units and non-residential square footage proposed in the project application, to calculate the increase in vehicle trips that would occur if the proposed project were to be developed.

To understand how the addition of units and non-residential square footage would influence person and vehicle trips to and from the project site, the inputs for the total proposed project were 99 "studio" (single occupancy) residential care suites, 10 "one-bedroom" (double occupancy) units, and 71,580 square feet of office use.[2] Under consultation with the department, office was used as a proxy for institutional use to estimate the amount of net new worker trips, which has components of similarly functioning land uses and employee travel activity. The inputs for the net new trips were 23 "studio" (single occupancy) residential care suites and 43,620 square feet of office.[3] The results are presented in Table 2 (next page) and in Appendix C - San Francisco Travel Demand Tool, Trip Generation Output table, June 4, 2024.

[2] For purposes of this calculation, the project sponsor provided an estimated breakdown of total proposed project's residential care unit square footage (70,000) and non-residential institutional square footage (71,580).

[3] The proposed project would increase the institutional uses at the site by 58,830 gross square feet, which is inclusive of the 23 net new residential care units that would be added. To more accurately calculate institutional use trip generation verses residential trip generation, the planning department separated residential uses from institutional uses by subtracting the average residential care unit size (70,000 square feet / 109 residential care units = 642 square feet) times 23 new units (642 * 23 = 14,766 residential square feet) from 58,830. The result was 43,620 (when rounded to the nearest ten).

Table 2 Travel Demand Estimate, PM Peak Vehicle Trips for Proposed Project

	Person Trips		Vehicle Trips	
Mode	Total	PM peak	Total	PM Peak
Auto	611	54	494	44
TNC/Taxi	142	13	95	8
Transit	302	27	--	--
Private Shuttle	146	13	--	--
Bike	51	5	--	--
Walk	360	329	--	--
Total Proposed Project	1613	144	588	52
Total Net New Trips	787	70	302	27

NOTE: Travel Demand inputs: Total proposed project: 99 studio units, 10 one-bedroom units and 71,580 square feet of office (proxy for institutional) at 3400 Laguna Street, Placetype 2. Net new project: 23 studio units and 43,620 square feet of office (proxy for Institutional) at 3400 Laguna Street, Placetype 2.

Overall, the proposed project would add an estimated 302 total vehicle trips to the adjacent streets and roadways, of which 27 p.m. peak vehicle trips are estimated from the addition of 23 residential care units (net increase of 58,830 square feet of institutional space).

Loading Impact Analysis

A project would have a significant effect on the environment if it would result in a loading demand during the peak hour of loading activities that could not be accommodated within proposed off-street loading facilities or within convenient on-street loading zones, and create potentially hazardous traffic conditions or significant delays affecting traffic, transit, bicycles or pedestrians.

The proposed project passenger loading space demand by land use is presented in Table 3, Project Passenger Loading Demand by Land Use. The proposed project would generate a passenger loading demand for one passenger loading space during the peak 15 minutes of the peak hour through the average peak period of passenger loading activity (5-8 p.m.). The project's passenger loading demand would be accommodated within the existing on-street, 45-foot-long white curb zone (approximately 2 loading spaces) on Laguna Street frontage and no loading deficit would occur. Additionally, the proposed project would develop an approximately 20-foot-long, two-lane off-street loading zone via the porte cochère in front of the proposed new Bay Building, which would provide universal access to the project site and additional passenger loading.

Table 3 Passenger Loading Demand by Land Use

	Proposed Project	
	Passenger Loading Demand (Spaces)	
Land Use	Peak Hour	Peak 15-minute
Institutional (Office used as proxy)	0.22	0.45
Residential (Studio units used as proxy)	0.05	0.10
Rounded Total	**1**	**1**

SOURCES: San Francisco Planning Department, 2019 TIA Guidelines, https://sfplanning.org/project/transportation-impact-analysis-guidelines-environmental-review-update, accessed May 14, 2024.

proposed project's freight and commercial loading demand is presented on Table 4, Project Freight Loading Demand by Land Use. The proposed project would generate demand of up to approximately one delivery and service loading activities per day which corresponds to a loading demand up to one loading spaces during the peak hour of freight loading activity through the average peak period of freight and commercial loading activity (11am-2pm). The proposed project would provide one off-street freight loading space accessible via Bay Street and parcel delivery could occur via the 20-foot-long off-street porte cochère in front of the new Bay Building. Additionally, the project's existing on-street, 45-foot-long white curb loading zone on Laguna Street has sufficient length to accommodate 2 vehicles, should simultaneous passenger and freight/commercial loading activity occur. As described by SFMTA's color curb program, any vehicle may use a white zone for active loading and are subject to the rules and restrictions for the effective days, hours, and time limits (i.e., parking for more than five minutes in white zone are subject to citation and towing).

Additionally, the project sponsor representing Heritage on the Marina provided an overview of the current freight loading operations at the site, including the number, frequency, and duration of freight loading events in a typical week and month (Appendix D). Based on the analysis conducted pursuant to the San Francisco Planning Department's Transportation Impact Analysis Guidelines and the information provided by the project sponsor, no freight and commercial loading deficit would occur.

Table 4 Freight Loading Demand by Land Use

	Proposed Project	
	Freight Loading Demand (Spaces)	
Land Use	Average Hour	Peak Hour
Institutional (Office used as proxy)	0.70	0.87
Residential	0.10	0.12
Rounded Total	1	1

SOURCES: San Francisco Planning Department, 2019 TIA Guidelines, https://sfplanning.org/project/transportation-impact-analysis-guidelines-environmental-review-update, accessed May 14, 2024.

If you have any questions related to this project's environmental evaluation, please call me at 652.628.7508.

Sincerely,


Megan Calpin
Senior Environmental Planner
Environmental Planning Division
San Francisco Planning Department

Appendices

Appendix A – Proposed Project Site Plan, 3400 Laguna Street, and Freight Loading Turn Templates
Appendix B – SDAT Letter, December 2022 and SDAT follow up email, June 2023
Appendix C - San Francisco Travel Demand Tool, Trip Generation Output table, June 4, 2024.
Appendix D – Heritage on the Marina Correspondence, June 2024

APPENDIX A

PROPOSED PROJECT SITE PLAN, 3400 LAGUNA STREET, AND FREIGHT LOADING TURN TEMPLATES



01 SITE PLAN - EXISTING
3/32" = 1'-0"

SITE LEGEND : EXISTING

- AREA OF MODIFIED LANDSCAPE
- BUILDING TO BE DEMOLISHED
- BUILDING TO REMAIN INTERIOR RENOVATION ONLY
- ACCESSIBLE PATH OF TRAVEL

HKS

ARCHITECT
HKS, INC.
350 N SAINT PAUL ST, SUITE 100
DALLAS, TX 75201- 4240

HERITAGE ON THE MARINA

OWNER
SAN FRANCISCO LADIES' PROTECTION AND RELIEF SOCIETY
3400 LAGUNA STREET
SAN FRANCISCO CA 94123-2271

OWNER'S CIVIL ENGINEER
KIMLEY HORN
2121 S EL CAMINO REAL
SAN MATEO, CA, 94403

INTERIM REVIEW ONLY

These documents are incomplete, and are released for interim review only and are not intended for regulatory approval, permit, or construction purposes.

Architect: XXXX XXXX
Arch. Reg. No.: XXXX
Date: XX/XX/XX

REVISION NO. | DESCRIPTION | DATE

HKS PROJECT NUMBER
24940.000

DATE
05.15.2023

ISSUE
PROJECT STATUS

SHEET TITLE
SITE -EXISTING

SHEET NO.
A1.10

© 2022 HKS, INC.

PLOT DATE: 11/1/2024 7:59:51 PM TEMPLATE VERSION: 21.0.0.20200831

SITE LEGEND : NEW CONSTRUCTION

1. REAR YARD SETBACK; WILL COMPLY VIA CUP PROCESS
2. PERMEABLE PAVERS
3. CAR SHARE SPACE: AS REQUIRED BY TABLE 166 OF SAN FRANCISCO PLANNING CODE A CAR SHARE SPACE WILL BE PROVIDED ON SITE OR WITHIN 800 FEET OF BUILDING SITE. LOCATION SHOWN IS A POSSIBLE LOCATION ONLY.

EXISTING BLDG. 4-STORY

EXISTING COURTYARD

EXISTING BLDG. 3-STORY

8' - 3 7/8"

23' - 10"

16' - 10 3/4"

220' - 8"

5' - 3 3/8"

5' - 7 7/8"

EXISTING 1 STORY COTTAGE - MINOR MAINTENANCE ONLY

EXISTING/RENOVATED PERRY BLDG. 4-STORY

BACK OF HOUSE AREA TRASH & RECYCLING ZONE

BIKE RACK

EXISTING CURB CUT

47' - 6 3/8"

UNIT TERRACES

60' - 3 5/8"

STREET PARKING

EXISTING TREE : SIGNIFICANT TREE TO REMAIN

DOCK CANOPY

DOCK

15' - 9"

INTERIOR GENERATOR ROOM

NEW CURB CUT

EXISTING TREE REMOVED; REPLACEMENT REQUIRED

PARKING GARAGE EXIT

ART WALLS

BUILDING ABOVE

20' - 0"

20' - 0"

DECORATIVE WATER FEATURE. VISUAL CONTINUATION TO THE INSIDE

PARKING GARAGE ENTRY

NEW COURTYARD: AT SAME LEVEL AS LEVEL 1

A4.02/04

65' - 0"

165' - 0"

BAY STREET

UPPER PLAZA

zero curb

NEW COMMUNITY ARRIVAL PLAZA

ACCESSIBLE RAMP

ENTRY VESTIBULE

NEW BAY BLDG. 4-STORY

A1.13/03

GARAGE LIMIT BELOW

NEW FRANCISCO BLDG. 4-STORY

FRANCISCO STREET

37' - 3 3/8"

low slope path to street front raised terrace.

BIKE RACK - 3

STREET PARKING

237' - 6"

237' - 6"

SIDE YARD SETBACK = 0'

SURFACE PARKING = 5 SPACES

45' - 0"

EXISTING COURTYARD: RENOVATION

43' - 4 5/8"

SIDE YARD SETBACK = 0'

HISTORIC MORGAN BLDG. 3 STORY

TRANSFORMER

ART GARDEN

A1.13/01

114' - 3 1/8"

66' - 10 1/8"

A1.13/02

NEW TRANSFORMER LOCATION; RECESS TRANSFORMER BELOW STREET LEVEL IF ALLOWED BY PG&E

EXISTING LANDSCAPE TO REMAIN

FRONT YARD 15' - 0"

STREET PARKING

PASSENGER LOADING (WHITE CURB)

ACCESSIBLE PARKING

LAGUNA STREET

01 PRJ -SITE
3/32" = 1'-0"

© 2022 HKS, INC.

HKS

ARCHITECT
HKS, INC.
350 N SAINT PAUL, ST., SUITE 100
DALLAS, TX 75201- 4240

HERITAGE ON THE MARINA

OWNER
SAN FRANCISCO LADIES' PROTECTION AND RELIEF SOCIETY
3400 LAGUNA STREET
SAN FRANCISCO CA 94123-2271

OWNER'S CIVIL ENGINEER
KIMLEY HORN
2121 S EL CAMINO REAL
SAN MATEO, CA, 94403

INTERIM REVIEW ONLY

These documents are incomplete, and are released for interim review only and are not intended for regulatory approval, permit, or construction purposes.

Architect: XXXX XXXX
Arch. Reg. No.: XXXX
Date: XX/XX/XX

REVISION NO. | DESCRIPTION | DATE

1 | PRJ Rev. 2 | 2024.01.10

HKS PROJECT NUMBER
24940.000


DATE
05.15.2023

ISSUE
PROJECT STATUS


SHEET TITLE
SITE - PROPOSED

SHEET NO.
A1.12


PLOT DATE: 4/26/2024 12:41:02 PM TEMPLATE VERSION: 21.0.0.20200831




EXISTING LOADING ENTRY




EXISTING LOADING DEPARTURE



PROPOSED LOADING ENTRY



PROPOSED LOADING DEPARTURE



SU-30

	feet
Width	: 8.00
Track	: 8.00
Lock to Lock Time	: 6.0
Steering Angle	: 31.8

VEHICLE DATA

SU-30 LOADING TRUCK
HERITAGE ON THE MARINA


NOTE: SU-30 VEHICLE CURRENTLY USED FOR PRODUCE DELIVERIES WEEKLY ON FRIDAY.

NORTH


GRAPHIC SCALE IN FEET
0 10 20 40

©2023


K:\BAY_JDE\197551001 - Heritage on the Marina - MAF\03 CAD\Exhibits\2023.02.14 - Loading Truck Turns Exhibit\Loading Truck Turns.dwg LOADING TRUCKS Oct 13, 2023




EXISTING LOADING ENTRY




EXISTING LOADING DEPARTURE



PROPOSED LOADING ENTRY



PROPOSED LOADING DEPARTURE




WB-40

	feet		
Tractor Width	: 8.00	Lock to Lock Time	: 6.0
Trailer Width	: 8.00	Steering Angle	: 20.3
Tractor Track	: 8.00	Articulating Angle	: 70.0
Trailer Track	: 8.00		

VEHICLE DATA

WB-40 LOADING TRUCK
HERITAGE ON THE MARINA

NOTE: WB-40 VEHICLE CURRENTLY USED FOR DELIVERIES WEEKLY ON MONDAY AND THURSDAY.



©2023

K:\BAY_JDE\197551001 - Heritage on the Marina - MAF\03 CADD\Exhibits\2023.02.14 - Loading Truck Turns Exhibit\Loading Truck Turns.dwg LOADING TRUCKS (2) Oct 13, 2023

APPENDIX B

SDAT LETTER, DECEMBER 2022 AND SDAT FOLLOW UP EMAIL, JUNE 2023

STREET DESIGN REVIEW

The Street Design Advisory Team (SDAT) is an inter-agency review body that provides street design guidance for projects subject to the streetscape and pedestrian improvement requirements established in the Better Streets Plan, or any project proposing work in the public right-of-way. SDAT includes representatives from The Planning Department, Department of Public Works, Municipal Transportation Agency (SFMTA), San Francisco Fire Department (SFFD), and the San Francisco Public Utilities Commission (SFPUC). SDAT reviewed the proposed project on November 7, 2022, and provides the following comments:

Site Conditions

(See Transportation Info Map http://sftransportationmap.org)

- ☐ Vision Zero Network High Injury
- ☒ Bicycle Network
- ☐ Green Connections Network
- ☐ Muni Corridor
- ☐ Transit Preferential Street
- ☒ Key Walking Street
- ☒ Curb Cut Restriction
- ☐ SFMTA or Public Works Projects

Conditions Requiring Street Design Review

- ☒ Planning Code 138.1 (required streetscape improvements per the Better Streets Plan)
- ☐ Vision Zero

Based on the information provided in the PPA Application:


- ☐ Development Application will not require SDAT review.
- ☒ Development Application will require SDAT review. The proposed project will require SDAT review upon submittal of the first Development Application. Any Development Application for a project requiring SDAT review shall include the required elements for a Streetscape Plan outlined in the Plan Submittal Guidelines here: http://forms.sfplanning.org/Plan_Submittal_Guidelines.pdf

REQUIRED STREETSCAPE FEATURES

Based on a preliminary interagency review, SDAT anticipates the project would be required to install the following streetscape features. Be aware that these recommendations are subject to change.

1. Bulbout (required per Planning Code Sec. 138.1)

- The project is required to install an extended wrap-around bulb-out at the intersection of Laguna Street and Bay Street. The bulb-out should project 6' into both the Laguna and Bay Street ROWs. The bulb out should extend to the existing curb cut on Bay Street.
- The project is also required to install a wrap-around bulb-out at the intersection of Laguna Street and Francisco Street. The bulb-out should project 6' into both Laguna and Francisco Street ROWs.
- Please note, there is an existing accessible parking space (blue zone) on Laguna Street near the intersection of Laguna and Francisco which will need to remain accessible. This will require installation of a curb ramp at the rear of the vehicle pull-up space in the bulb-out transition. Show the blue zone and the curb ramp serving the blue zone in the revised site plan.



- The project is responsible for any utility work associated the construction of the bulb-outs if needed.
- Turn Templates: With your next submission to SDAT, please submit the following turn templates for all bulbouts. Note that turn templates must be approved by SDAT prior to Planning entitlement.
    - Custom SFFD Engine
    - Custom SFFD Ladder

Follow-up for Bulbouts	Pre-entitlement/Next SDAT • Sponsor to submit revised plans to SDAT showing required bulbout(s) and relevant turn templates • Bulbout curb returns shall conform to SF Public Works' Standard Plan for Curb Bulbs. See: http://sfpublicworks.org/sites/default/files/87%2C175.pdf Pre- or Post-entitlement • Obtain relevant permits from BSM www.sfpublicworks.org/services/permits

2. Curb Cuts/ Driveways

- SDAT encourages the project team to consider single directional traffic flow for each of the curb cuts along Bay Street. This would allow for a reduce curb cut width which would minimize conflicts with pedestrian movement. Please note that all exit movements would be right turn only.
- Per Planning Code Section 155(l), driveways crossing sidewalks shall be no wider than necessary for ingress and egress, and shall be arranged, to the extent practical, to minimize the width and frequency of curb cuts, to maximize the number and size of on-street parking spaces available to the public, and to minimize conflicts with pedestrian and transit movements.
- Turn Templates: Vehicles may not be able to enter the proposed western driveway and turn into the proposed parking garage. With your next submission to SDAT, please submit turn templates for passenger vehicles accessing the parking garage to confirm.

3. Off-Street Loading

- Please clarify how the loading dock will work including describing the anticipated volume of delivery trucks, time of day deliveries that are likely to occur and size of vehicles that will serve the project
- The proposed passenger loading zone and accessible parking shall be accessible and comply with the requirements of California Building Code Chapter 11B. There shall be an accessible route from the passenger loading zone to ground-floor entrances. A detectable separation is required to separate the accessible route from the vehicular way (raised curb 4-inch minimum height, 3-ft depth detectable warnings, and/or a railing.

Follow-up for curb cuts, off-street parking and loading	Pre-entitlement/Next SDAT submittal • Include revised plans showing reduced curb cut width • Include revised plans showing a scaled freight vehicle parked within the off-street loading area • Submit loading demand analysis and loading operations plan • Submit turn templates for passenger vehicles accessing the parking garage and trucks accessing the loading dock
Contacts	Coordinate with your assigned Planner


4. On-street Passenger Loading

- The existing passenger loading zones (white zone) on the Laguna Street and Francisco Street frontages shall be accessible and comply with the requirements of California Building Code Chapter 11B and Standard Accessible Passenger Loading Zone Drawings. There shall be an accessible route from the passenger loading zone to ground-floor entrances. The white zone on Laguna Street could also be moved to Bay Street, but this relocation would require coordination with relevant agencies including SFMTA Color Curb Program and Public Works Disability Access Coordinator.
- Refer to Standard Accessible Passenger Loading Zone Drawings for technical requirements: https://sfgov.org/mod/sites/default/files/Documents/Bulletin10_PassengerLoadingZones.pdf
- Show the proposed Accessible Passenger Loading Zone geometry on the revised site plan.
- The sponsor shall set up a meeting with Paul Kniha (paul.kniha@sfmta.com), SFMTA Color Curb Program Manager, and Karina Lairet (karina.lairet@sfdpw.org), Associate Engineer with the Public Works Disability Access Coordinator, to discuss the project's loading needs and corresponding accessibility requirements.

Follow-up	Pre-entitlement/Next SDAT • Sponsor to submit written statement to Planning expressing intention to follow-up on this item • If SDAT requests only Commercial or Passenger Loading, or Accessible Passenger Loading, sponsor to meet with SFMTA Loading Team to coordinate design of loading zone(s). Post-entitlement (Post-Certificate of Occupancy) • Sponsor to apply for on-street loading zones from the SFMTA permits from SFMTA https://www.sfmta.com/online-color-curb-application)
Contacts	Karina Lairet (karina.lairet@sfdpw.org), Associate Engineer with the Public Works Disability Access Coordinator Paul Kniha (paul.kniha@sfmta.com), SFMTA Color Curb Program Manager

5. Street Trees

- The project is required to install street trees along all street frontages. Please coordinate with SF Public Works Bureau of Urban Forestry for guidance on spacing of tree basins.
- The existing trees along Bay and Francisco shall remain unless determined otherwise by SF Public Works Bureau of Urban Forestry (BUF). Any proposed new, removed, or relocated street trees and/or landscaping within the public sidewalk may require a permit from the Bureau of Urban Forestry (BUF).
- Below is a diagram where the new curb cut to the east is proposed to be located. There is a tree that is protected as a significant tree which needs to be preserved (or removal application submitted/permit issued if unable to protect tree). BUF strongly recommends protecting this native oak tree. See diagram below. Possible consideration could also be given to shifting the driveway even a few feet to the west to reduce impacts to this significant oak tree.



Follow-up	Pre-entitlement/Next SDAT • Sponsor to submit written statement to Planning expressing intention to follow-up on this item • Submit plans that differentiate existing trees from new trees • Submit revised plans that address tree placement comments above Post-entitlement • Sponsor to obtain any required permits from Public Works Bureau of Urban Forestry
Contacts	Public Works Bureau of Urban Forestry, urbanforestry@sfdpw.org, 628-652-8733

6. Street Lighting

- If existing lighting conditions on fronting the project site do not meet City standards, the project will be required to upgrade street lighting and/or pedestrian lighting. To determine if lighting improvements are required, the sponsor will need to provide photometric studies for street lighting plans to the SFPUC.

Follow-up	Pre-entitlement/Next SDAT • Sponsor to submit written statement to Planning expressing intention to follow-up on this item and confirm that Sponsor has reviewed the "Standard SDAT Comments" (see the end of this document) Post-entitlement • Projects are required to submit proposed street lighting plans and photometric studies to the Public Works Bureau of Street Use and Mapping (BSM) prior to issuance of the Streetscape Permit
Contacts	SFPUC Streetlights Division, Streetlights@sfwater.org

7. Transformer

- If a new electrical power transformer is required by PG&E to provide power to the building, please continue to show the location of the transformer room on the plans for SDAT review. Should the project wish to install an electrical transformer within the public right-of-way, be aware that sidewalk vaults are considered an exception by SF Public Works Bureau of Street Use & Mapping (BSM).

Follow-up	Pre-entitlement/Next SDAT • Sponsor to show proposed transformer locations on plans to be submitted and approved by SDAT • Coordinate with SFPUC or PG&E to ensure proposed transformer location meets relevant standards.
Contacts	• Transformer Location (ROW v. Private Property): Coordinate with your assigned Current Planner on this item • Transformer Location Technical Feasibility: Coordinate with electrical power utility (SFPUC or PG&E) and Public Works BSM.

ADDITIONAL INFORMATION REQUIRED FOR NEXT SDAT REVIEW

- ☐ Existing/proposed curb cuts and curb cuts to be removed
- ☐ Street names
- ☒ Dimensions of existing and proposed sidewalk and curb extensions on plans
- ☒ Dimensions of existing and proposed curb cuts on plans
- ☐ Dimensions of existing and proposed transit stops
- ☒ Site plan with streetscape features (e.g., bulbouts, trees, transit shelters, benches, bike racks)
- ☒ Proposed street tree locations
- ☐ Adjacent ROW widths
- ☒ Locations of existing utility poles and hydrants
- ☒ Turn templates for bulbouts
- ☐ Curb-to-curb section, including dimensions of tree wells and path of travel
- ☒ Proposed transformer vault location
- ☒ A written statement clarifying that Standard SDAT Comments have been reviewed

STANDARD SDAT COMMENTS

For your next SDAT submittal, please review the “Standard SDAT Comments” which can be found on the SDAT website (https://sfplanning.org/project/street-design-advisory-team), and include a written statement clarifying that this task has been completed and that all plans are consistent with guidelines/standards enumerated in the "Standard SDAT Comments”.

From:	Delumo, Jenny (CPC)
To:	Poling, Jeanie (CPC)
Subject:	FW: NO SDAT needed for 3400 Laguna + notes to convey
Date:	Wednesday, September 20, 2023 11:28:59 AM

Jenny Delumo, AICP (she/hers)
Senior Planner and Transportation Review Team Lead
Environmental Planning Division

San Francisco Planning
49 South Van Ness Avenue, Suite 1400, San Francisco, CA 94103
Direct: 628.652.7568 | www.sfplanning.org
San Francisco Property Information Map

From: Look, Jessica (CPC) <jessica.look@sfgov.org>
Sent: Friday, June 09, 2023 4:12 PM
To: Caldwell, Ben (CPC) <ben.caldwell@sfgov.org>; Horn, Jeffrey (CPC) <jeffrey.horn@sfgov.org>
Cc: Shaw, Jeremy (CPC) <jeremy.shaw@sfgov.org>
Subject: Re: NO SDAT needed for 3400 Laguna + notes to convey

comments added to podio..

Jessica Look, AICP | Senior Planner

Citywide Division

San Francisco Planning
49 South Van Ness Avenue, Suite 1400, San Francisco, CA 94103
Direct: 628.652.7455 | www.sfplanning.org
San Francisco Property Information Map

From: Caldwell, Ben (CPC) <ben.caldwell@sfgov.org>
Sent: Wednesday, June 7, 2023 11:36 AM
To: Horn, Jeffrey (CPC) <jeffrey.horn@sfgov.org>; Look, Jessica (CPC) <jessica.look@sfgov.org>
Cc: Shaw, Jeremy (CPC) <jeremy.shaw@sfgov.org>
Subject: NO SDAT needed for 3400 Laguna + notes to convey

Hi Jeff,

We just took a look at 3400 Laguna's resubmittal for possible SDAT next week and there are couple remaining concerns but overall we believe it adequately satisfies our previous SDAT comments for Planning's purposes and therefore does not need to return for a full SDAT 2nd meeting.

Jessica wrote the previous letter, but couldn't make our internal meeting today, so I'm passing along these notes in her stead. We would like to make sure the following 2 comments are conveyed to the project sponsor in your plan check letter:

- The curb radii for both new bulbouts are unnecessarily large and should be reduced. But SDAT will work with Public Works, MTA, and Fire as necessary to address this as best we can without needing to see another submittal. Final design of the curb radii will be ultimately finalized the SIP process.
- Our comment to add trees on all frontages still stands. The sponsor did not add them on the Laguna side. There may be historic preservation issues preventing them from adding them. If so, HP is saying one thing but BUF is saying another. This is in BUF's court now to hammer out with HP and the project sponsor.

Jessica, if you could please add these notes to Accela to document them, that would be much appreciated.

Also note, re: your notes in the calendar sign-up:

- SDAT elected not to say anything about the porte-cochere previously, so we wouldn't do so now.
- We only recommended driveway changes previously, and the changes made are an improvement. Final design of the curb cuts will be worked out during the SIP.

Thanks, and let me know if anyone has questions.

Jeff, if you're all good with the above, please remove the project from the SDAT calendar for next week if you don't mind.

Ben Caldwell, AICP, Urban Designer/Planner
City Design Group/Citywide Planning
San Francisco Planning
49 South Van Ness Avenue, Suite 1400, San Francisco, CA 94103
Direct: 628.652.7443 | www.sfplanning.org
San Francisco Property Information Map

APPENDIX C

SAN FRANCISCO TRAVEL DEMAND TOOL, TRIP GENERATION OUTPUT TABLE, JUNE 4, 2024.

Travel Demand: Total Proposed Project (109 units and 71,580 square feet of office (proxy for institutional use)

SAN FRANCISCO TRAVEL DEMAND TOOL INFO

WEBSITE VERSION: 0.3.2
DATA VERSION: 0.3

PROJECT LOCATION ATTRIBUTES

Address: 3400 laguna st
District: Marina/WesternMarket
Place Type: Urban medium density
City: San Francisco

SELECTED FILTERS

Time Period: pm
Purpose: work and non-work
Direction: inbound and outbound
Distribution Method: place-type

Average vehicle occupancy

Landuse	District AVO	Place Type	City AVO
Residential	1.3	1.5	1.5
Hotel	1.4	1.5	1.7
Retail	1.4	1.5	1.7
Supermarket	1.4	1.5	1.7
Office	1.2	1.2	1.2
Restaurant	1.4	1.5	1.7
Composite	1.4	1.5	1.7

Total Trips Generated by Land Use and Time

Landuse	Amount	Unit	Daily Perso	Daily Perso	PM Person	PM Person Trips
Residential	109	Bedrooms	4.5	490.5	0.4	43.6
Hotel	null	Rooms	8.4	0	0.6	0
Retail	0	1K Square	150	0	13.5	0
Supermarket	0	1K Square	297	0	21.7	0
Office	71.58	1K Square	15.7	1123.8	1.4	100.2
Restaurant	0	1K Square	200	0	27	0
Composite	0	1K Square	600	0	81	0
Total				1614.3		143.8

Mode Split Distribution

Landuse	Auto	TNC/Taxi	Transit	Private Shu	Walk	Bike
Residential	0.389	0.035	0.19	0.003	0.343	0.039
Hotel	0.269	0.157	0.147	0.042	0.384	0
Retail	0.259	0.014	0.118	0.005	0.576	0.028
Supermarket	0.259	0.014	0.118	0.005	0.576	0.028
Office	0.374	0.111	0.186	0.129	0.171	0.028
Restaurant	0.259	0.014	0.118	0.005	0.576	0.028
Composite	0.259	0.014	0.118	0.005	0.576	0.028

Total Trips by Mode


Mode	Total Persc	Filtered Pe	Total Vehic	Filtered Vehicle Trips
Auto	611.1	54.4	493.6	44
TNC/Taxi	141.9	12.6	94.6	8.4
Transit	302.2	26.9		
Private Shuttle	146.4	13.1		
Walk	360.4	32.1		
Bike	50.6	4.5		
Total (in bold)	**1613**	**144**	**588**	**52**

auto Person Trips Distribution by District

Landuse	Downtown SoMa		Marina/We	Mission/	Bayshore	Richmond	Sunset	Islands	South Bay	East Bay	North Bay	OuterMission/Hills
Residential	1.3	0.7	5.8	2.6	0.1	1.4	0.5	0	2	0.7	0.6	1.3
Hotel	0	0	0	0	0	0	0	0	0	0	0	0
Retail	0	0	0	0	0	0	0	0	0	0	0	0
Supermarket	0	0	0	0	0	0	0	0	0	0	0	0
Office	3.2	0.6	4.1	3.6	0.1	3.1	3	0	10	5.3	2.5	1.8
Restaurant	0	0	0	0	0	0	0	0	0	0	0	0
Composite	0	0	0	0	0	0	0	0	0	0	0	0
Total	4.5	1.3	9.9	6.2	0.2	4.5	3.5	0	12	6	3.1	3.1

auto Vehicle Trips Distribution by District

Landuse	Downtown SoMa		Marina/We	Mission/	Bayshore	Richmond	Sunset	Islands	South Bay	East Bay	North Bay	OuterMission/Hills
Residential	0.9	0.5	4	1.8	0.1	0.9	0.3	0	1.4	0.5	0.4	0.9
Hotel	0	0	0	0	0	0	0	0	0	0	0	0
Retail	0	0	0	0	0	0	0	0	0	0	0	0
Supermarket	0	0	0	0	0	0	0	0	0	0	0	0
Office	2.8	0.5	3.5	3.1	0.1	2.7	2.6	0	8.7	4.6	2.2	1.6
Restaurant	0	0	0	0	0	0	0	0	0	0	0	0
Composite	0	0	0	0	0	0	0	0	0	0	0	0
Total	3.6	1	7.5	4.9	0.2	3.7	2.9	0	10	5.1	2.6	2.4



Travel Demand: New New Additions (23 units and 43,620 square feet of office (proxy for institutional use)

SAN FRANCISCO TRAVEL DEMAND TOOL INFO

WEBSITE VERSION: 0.3.2
DATA VERSION: 0.3

PROJECT LOCATION ATTRIBUTES

Address: 3400 Laguna
District: Marina/WesternMarket
Place Type: Urban medium density
City: San Francisco

SELECTED FILTERS

Time Period: pm
Purpose: work and non-work
Direction: inbound and outbound
Distribution Meth place-type

Average vehicle occupancy

Landuse	District AVO	Place Type	City AVO
Residential	1.3	1.5	1.5
Hotel	1.4	1.5	1.7
Retail	1.4	1.5	1.7
Supermarket	1.4	1.5	1.7
Office	1.2	1.2	1.2
Restaurant	1.4	1.5	1.7
Composite	1.4	1.5	1.7

Total Trips Generated by Land Use and Time

Landuse	Amount	Unit	Daily Perso	Daily Perso	PM Person	PM Person Trips
Residential	23	Bedrooms	4.5	103.5	0.4	9.2
Hotel	null	Rooms	8.4	0	0.6	0
Retail	0	1K Square I	150	0	13.5	0
Supermarket	0	1K Square I	297	0	21.7	0
Office	43.62	1K Square I	15.7	684.8	1.4	61.1
Restaurant	0	1K Square I	200	0	27	0
Composite	0	1K Square I	600	0	81	0
Total				788.3		70.3

Mode Split Distribution

Landuse	Auto	TNC/Taxi	Transit	Private Shu	Walk	Bike
Residential	0.389	0.035	0.19	0.003	0.343	0.039
Hotel	0.269	0.157	0.147	0.042	0.384	0
Retail	0.259	0.014	0.118	0.005	0.576	0.028
Supermarket	0.259	0.014	0.118	0.005	0.576	0.028
Office	0.374	0.111	0.186	0.129	0.171	0.028
Restaurant	0.259	0.014	0.118	0.005	0.576	0.028
Composite	0.259	0.014	0.118	0.005	0.576	0.028

Total Trips by Mode


Mode	Total Persc	Filtered Pe	Total Vehic	Filtered Vehicle Trips
Auto	296.4	26.4	249	22.2
TNC/Taxi	79.6	7.1	53.1	4.7
Transit	147	13.1		
Private Shuttle	88.7	7.9		
Walk	152.6	13.6		
Bike	23.2	2.1		
Total (in bold)	**788**	**70**	**302**	**27**

auto Person Trips Distribution by District

Landuse	Downtown SoMa		Marina/We	Mission/	Bayshore	Richmond	Sunset	Islands	South Bay	East Bay	North Bay	OuterMission/Hills
Residential	0.3	0.2	1.2	0.5	0	0.3	0.1	0	0.4	0.1	0.1	0.3
Hotel	0	0	0	0	0	0	0	0	0	0	0	0
Retail	0	0	0	0	0	0	0	0	0	0	0	0
Supermarket	0	0	0	0	0	0	0	0	0	0	0	0
Office	2	0.4	2.5	2.2	0.1	1.9	1.9	0	6.1	3.2	1.5	1.1
Restaurant	0	0	0	0	0	0	0	0	0	0	0	0
Composite	0	0	0	0	0	0	0	0	0	0	0	0
Total	2.2	0.5	3.7	2.8	0.1	2.2	1.9	0	6.5	3.4	1.7	1.4

auto Vehicle Trips Distribution by District

Landuse	Downtown SoMa		Marina/We	Mission/	Bayshore	Richmond	Sunset	Islands	South Bay	East Bay	North Bay	OuterMission/Hills
Residential	0.2	0.1	0.8	0.4	0	0.2	0.1	0	0.3	0.1	0.1	0.2
Hotel	0	0	0	0	0	0	0	0	0	0	0	0
Retail	0	0	0	0	0	0	0	0	0	0	0	0
Supermarket	0	0	0	0	0	0	0	0	0	0	0	0
Office	1.7	0.3	2.1	1.9	0.1	1.7	1.6	0	5.3	2.8	1.3	1
Restaurant	0	0	0	0	0	0	0	0	0	0	0	0
Composite	0	0	0	0	0	0	0	0	0	0	0	0
Total	1.9	0.4	3	2.3	0.1	1.9	1.7	0	5.6	2.9	1.4	1.1



Freight Delivery Information Provided by Project sponsor

	M	T	W	Th	F	S	S
Vendor 1	--	30-45 min	--	--	30-45 min	--	
Vendor 2	30 min	--	30 min	30 min	--	30 min	
Vendor 3	15 min (5:30 am)	--	--	15 min (5:30 am)	--	15 min (5:30 am)	
Vendor 4	30-45 min						
Vendor 5	Once per month, day varies, 30-45 min						
Vendor 6	Less than once per month, day varies, 20 min						

Note: Delivery times are variable with each vendor. Vehicle lengths are consistent by vendor. The largest vehicles are 26 foot single axle trucks, the smallest are commercial delivery vans.

Maneuvering: [Bay] street is generally not closed for any length of time. The time the street is blocked is just time enough to line up and back the truck to the dock. Following construction of our proposed project, this maneuver will be slightly different with the new layout of the building, but again the street impact will be the same or less with the angle of the new dock.There is not a flagger. Trucks block traffic for a short time while they align with the dock. Once they back in there is no blocking of the street.

Passenger and Freight Loading Demand using San Francisco Transportation Impact Analysis Guidelines

1 What is the total square fotage per land use?

Office	71,580	new total
Residential	70,000	new total

2 What are the land use loading demand rates

Office	0.21	per 1000sf
Residential	0.03	per 1000sf

3 What is the daily delivery trip demand rate calcuation (turnover) - R

Office	15.0318
Residential	2.1

4 What is the average hour loading demand

Office	0.70	
Residential	0.10	
	0.793	1 space

5 What is the peak hour loading demand

Office	0.87	
Residential	0.12	
	0.99	1 spaces

APPENDIX D

HERITAGE ON THE MARINA CORRESPONDENCE, JUNE 2024

RE: 3400 Laguna - additional data request for sponsor team

Murphy, Alan H. (Perkins Coie) <AMurphy@perkinscoie.com>

Mon 6/3/2024 4:25 PM

To:Theresa Wallace <Theresa.Wallace@lsa.net>;Calpin, Megan (CPC) <megan.calpin@sfgov.org>;Eric Jacobs <eric@gbasf.com>; Frank Rockwood <frank@rockwoodpacific.com>
Cc:Range, Jessica (CPC) <jessica.range@sfgov.org>;Brent Rosenwald <Brent.Rosenwald@lsa.net>

2 attachments (1 MB)

HOTM Delivery Memo Rev 1.pdf; SDAT_3400 Laguna_ 2022_12_2.pdf;

Hi all,

This email responds to Megan's five data requests for transportation analysis, below. Our responses follow each item in bold. Under separate cover, either later today or tomorrow, we'll provide responses to the items in the Excel spreadsheet Theresa circulated on Friday.

From Megan: I have a few additional data requests for transportation analysis. Could you please:

- separate out, if possible, the square footage of residential care *units from the common institutional gross square footage?* Please also clarify how many of the 109 residential care suites are single or double occupancy.
  [Yes. As you know, there is no distinction in land use between these types of areas. That said, solely for purposes of obtaining a more accurate transportation analysis, the project will include approximately 70,000 square feet within residential care units, while the remainder of project square footage will be common institutional space. Of the 109 total units, approximately 10 may have double occupancy.]
- describe existing loading conditions and operations - is there a flagger for the truck backing in to the loading space and at what time of day do these type of deliveries occur? How many deliveries per day? Are the hours of delivery consistent or variable? Are the vehicle types consistent or variable?
  [Please see the attached memo from Jon Casey.]
- clarify the existing closures on Bay Street that occur due to loading - of the 9 closures, how long is the average closure for? (30 minutes each?)
  [Please see the attached memo from Jon Casey.]
- provide documentation of meetings / communications with SFMTA regarding accessible passenger loading or other SDAT related comments for my records.
  [There have not yet been communications with SFMTA regarding passenger loading. For your records, please see the attached SDAT memo.]
- provide the length of the proposed porte cochere loading space.
  [Over 20 feet of passenger loading space would be available beneath the proposed porte cochere. Two cars could be loaded undercover, side-by-side. There also would be space for four additional cars to queue in the new driveway outside the covered loading area.]

Please let us know if you have any further questions on these items.

Alan

Alan Murphy | Perkins Coie LLP
PARTNER
505 Howard Street, Suite 1000
San Francisco, CA 94105-3204
D. +1.415.344.7126
E. AMurphy@perkinscoie.com

MEMO
Prepared by Jon Casey, CFO / Compliance Officer
May 30, 2024

Regarding questions from San Francisco Planning on loading conditions and operations, and street closures due to loading at Heritage on the Marina.

Specifically, this memo will answer the following two questions:

1. Describe existing loading conditions and operations:
    a. Is there a flagger for the truck backing into the loading space and at what time of day do these type of deliveries occur?
    b. How many deliveries per day?
    c. Are the hours of delivery consistent or variable?
    d. Are the vehicle types consistent or variable?
2. Clarify the existing closures on Bay Street that occur due to loading - of the 9 closures, how long is the average closure for? (30 minutes each?)

Response to question 1:

    a. There is not a flagger. Trucks block traffic for a short time while they align with the dock. Once they back in there is no blocking of the street. The delivery times vary depending on the vendor and the individual delivery.
    b. Please see the schedule below.
    c. Variable with the vendor and the deliveries for that day
    d. Consistent by vendor. The largest vehicles are 26 foot single axle trucks, the smallest are commercial delivery vans.

Here are details on current deliveries received throughout the week on the following customary delivery schedule:

Sysco: frequency of delivery, Tues & Fri, time spent at the location ~30-45 mins
Vesta: frequency of delivery, Mon, Wed, Thurs & Sat, time spent at the location ~30 mins
Le Boulanger: frequency of delivery, Mon, Thurs & Sat, time spent at the location ~15 mins, early morning ~5:30am.

Alsco: frequency of delivery, Mon & Thurs, time spent at the location ~30-45 mins
Waxie: frequency of delivery, once per month, day varies, time spent at location ~30-45 mins
Alhambra Water: frequency of delivery less than once a month, time spent at location ~20 mins

Question 2:

The street is generally not closed for any length of time. The time the street is blocked is just time enough to line up and back the truck to the dock. Following construction of our proposed project, this maneuver will be slightly different with the new layout of the building, but again the street impact will be the same or less with the angle of the new dock.

If there are any additional details required for this request, please let us know.